

ADDENDUM posted 07/19/2016 2:30 p.m.

Northwest Road Culvert Relining Project Bid

Addendum #1:

On the Prevailing Wage Sheet, under Description of Work should read:
“Culvert Relining-Install 196’ x 54” Snap-Tite”.

Addendum #2:

All environmental permitting is the responsibility of the Town of Westhampton.

Addendum #3:

In **Scope of Services**; **Specifications** change as follows (underlined):

2. Materials

I. End Treatment -The upstream/inlet end of the new liner pipe shall be fitted with a flow enhancement device to reduce inlet control effects. The device shall be HDPE material, or fiberglass, and have a connector included for connection to the liner pipe. The opening at the end of the device shall be larger than the ID of the host pipe. 3rd Party Test data shall be provided to show improvement of flow by at least 30% at 2 feet of headwater depth or an entrance loss coefficient (K) of approximately 0.2 for outlet control conditions. The device shall be the Hydro-Bell or approved equal. The HydroBell shall be secured at the joint with the pipe with either a concrete collar or native boulders placed so that the inlet is cohesive and secured.